BRUHAT BANGALORE MAHANAGARA PALIKE

DASARAHALLI ZONE

Name of Work: Detailed Estimate for the Work of Annual Maintenance of Borewell for Chikkasandra and Medharahalli, in Dasarahalli Zone, Dasarahalli Division, Ward No.12, Shettyhalli Sub-Division, - for the year 2013-14.

Sl. No.	Particulars	Unit	Materials Required for 7.5 HP Repair			Materials Required for 10 HP Repair			Materials Required for 12.5 HP Repair		
			Qty	Rate	Amount	Qty	Rate	Amount	Qty	Rate	Amount
1	2	3	4	5	6	7	8	9	10	11	12
	PART - A										
A	**MOTOR REWINDING**										
1	Repairs to Motor: Rewinding of submersible pumpsets with copper insulation wire of suitable guage as per ISI specification with guarantee of 6 months BWSSB SR Page 2013-14, Page No.83, Item No.A(3)	No.	1	3822.50	3822.50	1	4785.00	4785.00	1	5855.00	5855.00
B	**PUMP REPAIRS**										
	Replacement of pump parts the following main components of submersible pumpsets requiring replacement										
2	Pump bowls BWSSB SR Page 2013-14, Page No.83, Item No.B(1)	No.	16	308.00	4928.00	20	308.00	6160.00	30	308.00	9240.00
3	Intermediate piece (I.P) with leaded bronze bush BWSSB SR Page 2013-14, Page No.83, Item No.B(2)	No.	1	715.00	715.00	1	715.00	715.00	1	715.00	715.00
4	Oil seal steel bush BWSSB SR Page 2013-14, Page No.83, , Item No.B(3)	No.	2	121.00	242.00	2	121.00	242.00	2	121.00	242.00
5	Oil seal steel bush BWSSB SR Page 2013-14, Page No.83, Item No.B(4)	No.	1	132.00	132.00	1	132.00	132.00	1	132.00	132.00